

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23659-00-00
Spot: E2NWNSE Sec/Twnshp/Rge: 12-13S-14W
2310 feet from S Section Line, 870 feet from E Section Line
Lease Name: SEIRER-BREIT A Well #: 1
County: RUSSELL Total Vertical Depth: 3320 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/14/2010 10:00 PM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: DOUG Company: PROSPECT OIL & GAS CORPORATI Phone: (785) 483-6266

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 09/14/2010 11:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 3260' w/25 sxs.
2nd. Plug at 790' w/25 sxs.
3rd. Plug at 380' w/100 sxs.
4th. Plug at 285' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

RECEIVED
SEP 24 2010
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM