

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23030-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 8-35S-4E  
3999 feet from S Section Line, 2324 feet from E Section Line  
Lease Name: BROCE Well #: 10  
County: COWLEY Total Vertical Depth: 3565 feet

Operator License No.: 33293  
Op Name: PRYOR, VICTOR W., JR.  
Address: PO BOX 898  
HOLDENVILLE, OK 74848

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3250		
SURF	8.625	236		120 sx
PROD	5.5	3517		600 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2010 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 763-7748

Proposed Plugging Method: AS PER KCC RULES & REGS, CIBP SET 50' ABOVE PERFS W/2 SXS CEMENT. PERF & CIRCULATE CEMENT FROM 300'-0'

Plugging Proposal Received By: DUANE KRUEGER  
Date/Time Plugging Completed: 10/15/2010 5:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3250'. DUMP BAILED 2 SXS CEMENT ON TOP. RIH W/TBG @ 300', ACID CEMENTING SERVICES, ESTABLISHED CIRCULATION & MIXED & PUMPED 45 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-15-2010, 5:00 PM CEMENT TICKET #10287.

Perfs:


Top	Bot	Thru	Comments
3300			CSG

Remarks: CEMENT @ SURFACE ON BACKSIDE 5-1/2" CASING.

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

RECEIVED  
NOV 02 2010  
KCC WICHITA