

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20991-00-01
Spot: SW Sec/Twnshp/Rge: 26-33S-32W
1220 feet from S Section Line, 3760 feet from E Section Line
Lease Name: CITY OF LIBERAL Well #: 1-26
County: SEWARD Total Vertical Depth: 6050 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5455		WITH 10 SX CMT
SURF	8.625	1601		WITH 475 SX CMT
PROD	4.5	5854	1705	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/18/2010 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: BLAINE FLAMING Company: QUINQUE OPERATING Phone: (405) 840-9876

Proposed Plugging Method: PUMP MUD DOWN 4-1/2 CSG. SET CIBP AT 5463'. PUMPED 10 SXS CMT. CUT 4-1/2 AT FREE BINT. LAY DOWN SAME. TIH WITH TBG AND PUMP 200# HULLS & 50 SX AT 1650'. PULL TBG TO 500' & PUMP 30 SX CMT. PULL TBG TO 33' & PUMP 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2010 11:25 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5455' WITH 10 SX CMT. RAN TBG TO 1650' & CIRCULATED GEL WATER WITH 5 SX GEL & 200# HULLS. 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 30 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5550	5554		
5511	5513		

Remarks: USED 60/40 POZMIX 4% GEL BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
AUG 30 2010
KCC DODGE CITY

RECEIVED
SEP 07 2010
KCC WICHITA