

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-20840-00-00  
Spot: W2NENWSW Sec/Twnshp/Rge: 21-31S-8W  
2310 feet from S Section Line, 990 feet from W Section Line  
Lease Name: BURGESS B Well #: 1  
County: HARPER Total Vertical Depth: 4390 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 912 N LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		225 SXS CMT
PROD	5.5	4380	2270	100 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2010 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SAND BACK 50 FT ABOVE THE PERFS OR OPEN HOLE AND CAP WITH 5 SKS OF CMT. 35 SKS OF CMT AT 1450. 35 SKS AT 950', CIRC CMT FROM 280-0'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/24/2010 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4300' AND CAP WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2270' AND PULLED TO 1450' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 280' WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4380	4390	CSG	OPEN HOLE

Remarks: QUALITY WELL SERVICE #5022 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

SEP 27 2010

KCC WICHITA

Form CP-2/3