

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23575-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 29-25S-11W
3685 feet from S Section Line, 4737 feet from E Section Line
Lease Name: HOSKINSON Well #: 1
County: STAFFORD Total Vertical Depth: 4200 feet

Operator License No.: 33530
Op Name: REIF OIL & GAS COMPANY LLC
Address: PO BOX 298
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	648		WITH 250 SX CMT
PROD	5.5	4190	3200	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2010 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SET CIBP @ 3900' & 2 SX CMT. LOAD HOLE WITH GEL WATER & PUMP 50 SX CMT AT 660' PLUG AT 270' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2010 9:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3900' & 2 SX CMT WITH DUMP BAILER. 1ST PLUG AT 672' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 276' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3960	3984		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

AUG - 3 2010

KCC DODGE CITY

RECEIVED

AUG 10 2010

KCC WICHITA