

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29082-01-00
Spot: SWNE Sec/Twnshp/Rge: 26-25S-18E
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: WALLS Well #: 1
County: ALLEN Total Vertical Depth: 1720 feet

Operator License No.: 33221
Op Name: ROXANNA PIPELINE, INC.
Address: 4600 GREENVILLE AVE STE 200
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	36		50 SX
T1	2.875	1616		
PROD	7.625	1720		370 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/28/2010 2:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: TOM GILBERT Company: ROXANNA PIPELINE, INC. Phone: (785) 466-1158

Proposed Plugging Method: THIS WELL HAS A 1482' MAIN BORE THAT'S HORIZONTAL BY 1300' AND TWO HORIZONTAL LATERALS IN THE RIVERTON. WE PLAN TO PUMP 35 SXS OF CEMENT FROM 1250-1350' ABOVE THE RIVERTON. WE PLAN TO LET IT SET 3 HRS. WE'LL TAG IT AND PUMP CEMENT UP TO 500' (STRAIGHT HOLE). FINALLY WE PLAN TO PULL UP AND FILL THE HOLE TO THE SURFACE W/ CEMENT.

Plugging Proposal Received By: JOHN ALMOND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2010 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

RAN PIPE TO 1250', SPOTTED 40 SACKS PORTLAND CEMENT, PULLED PIPE, LET SET, RAN PIPE BACK TO TAG CEMENT, CIRCULATE CEMENT TO SURFACE, PULL PIPE AND TOP OFF WELL WITH CEMENT.

RECEIVED
FEB 13 2011 JA
KCC Chanute Dist. #3

Perfs:

Top	Bot	Thru	Comments
1555	2277		2nd Lateral
1482	1807		1st Lateral

Remarks:

Plugged through: TBG

District: 03

Signed John Almond (TECHNICIAN)

RECEIVED
FEB 14 2011
KCC WICHITA