

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20553-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 32-15S-8W
2049 feet from S Section Line, 4703 feet from E Section Line
Lease Name: SVATY Well #: 2
County: ELLSWORTH Total Vertical Depth: 2641 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: 111 WHITTIER # 1000 PO BOX 783010
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	325		N/A
PROD	4.5	2640	2640	

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/26/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/26/2011 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 2590' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF @ 1239' AND PULL TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 600' AND PUMP 35 SX'S CEMENT. PULL CASING TO 375' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2640	2641	OH	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35770

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

FEB 08 2011

KCC WICHITA

Form CP-2/3