

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-08578-00-01
Spot: SWNENW Sec/Twnshp/Rge: 16-15S-13W
4158 feet from S Section Line, 3312 feet from E Section Line
Lease Name: BITTER Well #: 4A
County: RUSSELL Total Vertical Depth: 3281 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF		0		
PROD	4.5	3275	0	300 sxs

Well Type: EOR UIC Docket No: E07607.19 Date/Time to Plug: 02/16/2011 10:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2011 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2935' - pumped 75 sxs cement with 100# hulls.
Pulled tubing to 1830' - pumped 55 sxs cement with 100# hulls.
Pulled tubing to 1060' - pumped 75 sxs cement - cement circulated.
POOH. Hooked on and pumped 5 sxs cement.
Max. P.S.I. 350#.

Perfs:

Top	Bot	Thru	Comments
3083	3093		LKC
3000	3005		CIBP 3012
2928	2932		Plattsmouth

RECEIVED
FEB 24 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34146.

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN)

CM

Form CP-2/3

FEB 21 2011