

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-30186-00-00  
Spot: NWNE Sec/Twnshp/Rge: 9-14S-17W  
4963 feet from S Section Line, 770 feet from E Section Line  
Lease Name: SATURIN Well #: 2  
County: ELLIS Total Vertical Depth: 3588 feet

Operator License No.: 34318

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 176        | 0           | 150 SX   |
| PROD   | 4.5   | 3588       | 0           | 100 SX   |

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/17/2011 12:30 PM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO LLC

Phone: (785) 628-6101

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack - 8 sxs gel - 400# hulls.  
DV Tool at 1214' w/437 sxs.  
Pat Staab worked up lease.

Plugging Proposal Received By: PAT STAAB

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/17/2011 2:45 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Berexo RIH with tubing to 3400'.  
Allied rigged to tubing and pumped 8 sxs gel - followed with 45 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.  
Pulled tubing to 1650' - mixed and pumped 55 sxs cement with 100# hulls.  
Pulled tubing to 845'. Allied rigged to tubing and mixed and pumped 65 sxs cement with 100# hulls to circulate cement to surface.  
Pulled tubing. Topped off 4 1/2" casing with two sxs cement.  
Hole standing full.  
Rigged to 8 5/8" - pumped 5 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3558 | 3587 |      | Arbuckle |


RECEIVED  
FEB 24 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34148.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

FEB 21 2011