

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00518-00-01  
Spot: NENENE Sec/Twnshp/Rge: 15-12S-21W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: COTTON Well #: 2  
County: TREGO Total Vertical Depth: 4039 feet

Operator License No.: 6998  
Op Name: DOUBLE "K" OIL, INC.  
Address: 17053 390TH AVE  
ELLIS, KS 67637

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3948		
SURF	8.625	180	0	115 SX
PROD	4.5	4039	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2011 10:00 AM  
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC  
Proposal Rcvd. from: AVEN WEAVERLING Company: DOUBLE "K" OIL, INC. Phone: (785) 726-3321

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Casing likely parted at 1466'  
Went in with notched collar. Got to 761'.  
Went in with 3 7/8" bit - still not making hole.  
Went in with mill shoe - nothing - mudded up.  
Went in with 3 7/8" bit again - got to 1458' - then got hard and binding.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/15/2011 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perfs at 1000' - 180'.  
Ran tubing to 1466' - pumped 95 sxs cement - no hulls - good circulation of cement - pulled tubing out.  
Tied onto casing - pumped 60 sxs cement - good circulation out backside - shut in backside.  
Pumped 115 sxs cement down casing.  
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
4018	4022		ARBUCKLE
3942	3947		CONGLOMERATE
3918	3924		MARMATHON
3545	3550		TOPEKA

RECEIVED  
FEB 24 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4692.

Plugged through: TBG

District: 04

Signed   
(TECHNICIAN)

CM