

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-31528-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 29-23S-14W
4902 feet from S Section Line, 4968 feet from E Section Line
Lease Name: CADMAN UNIT Well #: 1
County: STAFFORD Total Vertical Depth: 4056 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	255		WITH 225 SX CMT
PROD	5.5	3885	1980	WITH 125 SX CMT

Well Type: EOR UIC Docket No: E15604.1 Date/Time to Plug: 02/03/2011 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3730' & 5 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2011 4:28 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3600' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 903' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 289' WITH 50 SX CMT. 3RD PLUG AT 36' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3780	3788		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

FEB 10 2011

KCC DODGE CITY

RECEIVED

FEB 15 2011

KCC WICHITA