

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-31531-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 30-23S-14W
4265 feet from S Section Line, 1710 feet from E Section Line
Lease Name: CADMAN UNIT Well #: 2
County: STAFFORD Total Vertical Depth: 3850 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	267		WITH 265 SX CMT
PLG	5.5	3815		
PROD	5.5	3849	1990	WITH 600 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2011 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3730' & 5 SX CMT. PLUG AT 930' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2011 12:22 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3550' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 932' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 34' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3787	3791		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

FEB 14 2011

KCC DODGE CITY

RECEIVED
FEB 23 2011
KCC WICHITA

Form 649/3