

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-31458-00-01
Spot: NWSESE Sec/Twnshp/Rge: 19-23S-14W
964 feet from S Section Line, 1008 feet from E Section Line
Lease Name: SHEPHERD Well #: 1
County: STAFFORD Total Vertical Depth: 3850 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	248		WITH 220 SX CMT
PROD	5.5	3849	2000	WITH 125 SX CMT

Well Type: EOR UIC Docket No: E15604.3 Date/Time to Plug: 02/14/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3730' & 5 SX CMT. PLUG AT 930' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2011 10:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3736' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 935' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 289' WITH 50 SX CMT. 3RD PLUG AT 36' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3786	3792		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

FEB 18 2011

KCC DODGE CITY

RECEIVED
FEB 23 2011
KCC WICHITA

Form CR-3