

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21958-00-00
Spot: E2SENESEW Sec/Twnshp/Rge: 5-25S-14W
1650 feet from S Section Line, 2360 feet from W Section Line
Lease Name: WILSON Well #: 2
County: STAFFORD Total Vertical Depth: 4376 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3735		WITH 2 SX CMT
CIBP		4000		WITH 2 SX CMT
SURF	8.625	349		WITH 225 SX CMT
PROD	5.5	4373	1037	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2011 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: SET CIBP @ 4080' & 2 SX CMT. SET CIBP @ 3710' & 2 SX CMT. RECOVER CASING TO 960' & PUMP 15 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2011 3:02 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4000' WITH 2 SX CMT. SET CIBP @ 3735' WITH 2 SX CMT. 1ST PLUG AT 930' WITH 14 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4138	4154		MISS
3767	3993		LANSING

Remarks: **COMPLIANCE ISSUE: YES NOV TA LTR** USED 60/40 POZMIX 4% GEL BY BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JAN 21 2011
KCC DODGE CITY

Signed Richard M. Lacey
RECEIVED (TECHNICIAN)
JAN 27 2011
1-27-11
KCC WICHITA

Form CP-100