

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21481-00-00
Spot: W2NENENE Sec/Twnshp/Rge: 36-16S-20W
4911 feet from S Section Line, 582 feet from E Section Line
Lease Name: BALDWIN Well #: 3-36
County: RUSH Total Vertical Depth: 3854 feet

Operator License No.: 33146
Op Name: HEMBREE ENERGY, LLC
Address: 1801 E 56TH AVE
HUTCHINSON, KS 67502

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	261		WITH 175 SX CMT
PROD	5.5	3850	0	WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: FRED J. HEMBREE Company: HEMBREE ENERGY Phone: (620) 728-1632

Proposed Plugging Method: SAND TO 3800' WITH 5 SX CMT. PLUG AT 1340' WITH 15 SX GEL & 50 SX CMT. PLUG AT 720' WITH 30 SX CMT. PLUG AT 290' WITH 30 SX CMT. PLUG AT 60' WITH 20 SX CMT. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2010 1:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3750'. RAN TBG TO 3640' & PUMPED 15 SX GEL & 10 SX CMT. 1ST PLUG PULLED TBG TO 1343' & PUMPED 45 SX CMT. 2ND PLUG PULLED TBG TO 720' & CIRCULATED CMT TO SURFACE WITH 50 SX CMT. PULLED TBG OUT OF HOLE & TOPPED 5 1/2" WITH 5 SX CMT. 3RD PLUG PRESSURE TESTED 8 5/8" X 5 1/2" TO 500 PSIG WITH 5 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
DEC 15 2010
KCC DODGE CITY

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED
DEC 20 2010
KCC WICHITA