

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20965-00-00
Spot: NENWSWNE Sec/Twnshp/Rge: 33-16S-30W
1600 feet from N Section Line, 2280 feet from E Section Line
Lease Name: BRAND C Well #: 1
County: LANE Total Vertical Depth: 4651 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3920		WITH 2 SX CMT
SURF	8.625	287		WITH 200 SX CMT
PROD	4.5	4066	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2010 3:00 PM
Plug Co. License No.: 7146 Plug Co. Name: CHEYENNE OIL SERVICES, INC.
Proposal Rcvd. from: MICHAEL POLLEY Company: HERMAN LOEB LLC Phone: (719) 342-5600

Proposed Plugging Method: SET CIBP @ 3900' WITH 2 SX CMT. LOAD CASING WITH WATER PRESSURE TEST CASING. RUN BOND LOG TO FIND CMT TOP. PERFORATE @ 735'. SPOT CMT AT ANHYDRITE. PULL TBG TO 700' & PUMP INTO PERFS, THEN TRY TO CIRCULATE CMT. IF CAN'T LOAD CASING WITH CMT WITH 50 SX CMT OUT CASING THEN PUT 150 SX CMT DOWN BACISKDE IF POSSIBLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2010 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN BOND LOG ON 12/28/10. TOC @ 740'. SET CIBP @ 3920' WITH 2 SX CMT. TEST CASING TO 300#. PERFORATE CASING AT 735', RUN TBG TO 2307' & SPOT 85 SX CMT. PULL TBG TO 760' & PUMP 10 BBL WATER PUMPING INTO PERFS @ 2 BBL/MINUTE @ 300#. PUMP 65 SX CMT & WENT ON VACUUM. PULL TBG & TIE ONTO CASING & PUMP 110 SX CMT & 150# HULLS. STILL ON VACUUM. TIE ONTO BACKSIDE & PUMP 140 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 100#. WAIT 3 HOURS & TOPPED OFF WITH 50 SX CMT. BACKSIDE STILL HAD PRESSURE ON IT.

Perfs:


Top	Bot	Thru	Comments
3962	3963		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
JAN 11 2011
KCC DODGE CITY

JAN 21 2011

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3