

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-10200-00-00  
Spot: NESW Sec/Twnshp/Rge: 1-35S-31W  
2014 feet from S Section Line, 3457 feet from E Section Line  
Lease Name: LAUDERBACK Well #: 1  
County: SEWARD Total Vertical Depth: 6400 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1450		
CIBP		5780		WITH 2 SX CMT
SURF	8.625	1420		WITH 800 SX CMT
PROD	4.5	6002	0	

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2010 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: MICHAEL POLLEY Company: HERMAN LOEB LLC Phone: (719) 846-3434

Proposed Plugging Method: CIBP @ 5800' WITH 2 SX CMT. LOAD & TEST CASING. PERFORATE @ 1450' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/09/2010 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*SQUEEZED PERFS 2638-2838', 3607-4668, 4997-5082'.\*\* CIBP @ 5780' WITH 2 SX CMT. ATTEMPT TO LOAD & TEST CASING. PUMPING INTO A CASING LEAK @ 1.8 BPM @ 500#. SET CIBP @ 1450'. TEST CASING TO 500# & HELD. PERFORATE @ 1430'. INJECTION RATE 3 BPM @ 200#. CIRCULATE MUD OUT ANNULUS. CIRCULATE WELL WITH CMT FROM 1430' TO 0' WITH 375 SX CMT. CASING & ANNULUS STAYED FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5824	5895		MORROW

RECEIVED  
DEC 30 2010  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
DEC 22 2010  
KCC DODGE CITY

Form CP-2/3