

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20200-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 31-31S-32W
4051 feet from S Section Line, 1235 feet from E Section Line
Lease Name: MORGAN Well #: 1
County: SEWARD Total Vertical Depth: 2727 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2600		WITH 2 SX CMT
SURF	8.625	650		WITH 200 SX CMT
PROD	4.5	2726	600	WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/22/2010 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: MICHAEL POLLEY Company: HERMAN LOEB LLC Phone: (719) 846-3434

Proposed Plugging Method: SET CIBP @ 2600' WITH 2 SX CMT. PERFORATE @ 680' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2010 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 2600' WITH 2 SX CMT. PERFORATE 4 1/2" @ 680'. ATTEMPTED TO BREAK CIRCULATION TO 4 1/2" X 8 5/8" ANNULUS BY PUMPING WATER DOWN 4 1/2". PUMPED 50 BBL WATER @ 2 BBL/M @ 500 PSI. NO BLOW OR SUCTION ON ANNULUS. MIXED HEAVY MUD & PUMPED 23 BBL MUD WITH 2 BBL FLUSH, NO BLOW OR SUCTION ON ANNULUS. PUMPED AT 1.5 BBL/M WITH PRESSURE @ 700 PSI. ISIP @ 450 PSI, DROPPED OFF TO 400 PSI AFTER 20 MINUTES. BLEED OFF 1/2 BBL FROM CASING, TIED ONTO ANNULUS TO ATTEMPT REVERSE CIRCULATE, PUMPED 11 BBL WATER INTO ANNULUS & DISCOVERED BRAIDEN HEAD HAD NO PACKING, JUST SLIPS, UNABLE TO PRESSURE UP. SDON. 12/23/10: RAN CMT BOND LOG & DISCOVERED WELL HAD CMT TO 630' FROM SURFACE. CUT 4 1/2" @ 600' & PULLED OUT OF HOLE. RIHWT TO 600' (UNABLE TO GET BACK INTO THE 4 1/2" CASING WITH TBG) CEMENTED WELL TO SURFACE WITH 175 SX CMT. 12/27/10: TOPPED OFF 8 5/8" CASING WITH 15 SX CMT. FILLED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2658	2664		KRIDER

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: .01

Signed


(TECHNICIAN)

RECEIVED

JAN 18 2011

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 21 2011

CONSERVATION DIVISION
WICHITA, KS