

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22545-00-00
Spot: NENWSWSW Sec/Twnshp/Rge: 21-15S-22W
1275 feet from S Section Line, 4750 feet from E Section Line
Lease Name: JUNE Well #: 4
County: TREGO Total Vertical Depth: 4270 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220	0	175 SX COMMON CMT 2% GEL, 3% CC
T1	2.875	4173		
DVT		1579		200 SX CMT SMDC
PROD	5.5	4268	0	350 SX CMT EA2 & SMDC

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/23/2010 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 200# hulls - 18 sxs gel.
Port collar at 1580' with 200 sxs cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2010 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4195' - pumped 18 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1616' - pumped 160 sxs cement - good circulation of cement.
Pulled tubing out - topped off with 20 sxs cement - full.
Tied onto backside - full.
Max. P.S.I. 500#. Shut in.

Perfs:

Top	Bot	Thru	Comments
4199	4206		CHEROKEE


Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4448.

RECEIVED
DEC 29 2010
KCC WICHITA

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

DEC 27 2010