

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20865-00-00  
Spot: NESENE Sec/Twnshp/Rge: 31-1S-32W  
1760 feet from N Section Line, 330 feet from E Section Line  
Lease Name: GERTIE KASTENS Well #: 31-1  
County: RAWLINS Total Vertical Depth: 4240 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 9915 W 21ST ST, STE B  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	306	0	185 SX CMT
T1	2.875	4166		
PC		2814		175 SX CMT
PROD	5.5	4238	0	175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2011 11:00 AM  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: MICHAEL J STANTON Company: IA OPERATING, INC. Phone: (785) 689-4609

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.  
Plug through casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/19/2011 1:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 306' w/185 sxs cement.  
5 1/2" production casing set at 4238' w/175 sxs cement.  
TD 4240'. Port collar at 2812' w/525 sxs cement.  
Well reported non-commercial.  
Connected to 5 1/2" production casing - pumped 50 sxs cement mixed with 300# hulls - followed with 9 sxs gel and 275 sxs cement.  
Connected to 8 5/8" surface casing - pumped 15 sxs cement.  
Max. P.S.I. 300#.  
Topped 5 1/2" production casing with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
4138	4141		j zone
4010	4015		c zone

RECEIVED  
JAN 24 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #40815.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

JAN 20 2011