

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Messman -Rinehart Oil Company 15-057-01683-00-00

Complete Address 1432 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name A. Staab Estate Well No. 1

Location C N/2 NW NE Sec. 1 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3630'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling, Inc.,

Address Boa 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 2:30 P Day 18 Month 11 Year 1970

The above well was plugged as follows:

Total Depth 3630' 8 5/8 csg set at 234' cwc 200 sk.

4 1/2 csg set at 3630' cw 40 sk cmt.

4 1/2 csg PBTD 3627 with top perf. ( 3598)

Filled 4 1/2 csg W/sd (3530-3627) Dumped 4 sk cmt W/dump bailer. (3500-3530)

Cutoff and recovered 2940' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 25 sk gel W/5 sk hulls, plug and 130 sk

50-50 poz W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bob F. Messner  
Well Plugging Supervisor

DATE 11/20/70

INV. NO. 2889-W