

P

Form CP-3

Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 23 1978
10-23-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 057 - 20613-00-01 (of this well)

Operator's Full Name R. P. Nixon Operations

Complete Address 207 W. 12th St., Hays, Kansas 67601

Lease Name Pfeifer Well No. 1

Location SW SW SE Sec. 15 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3699'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 19 Month 10 Year 1978

The above well was plugged as follows:

Total Depth 3699' 8 5/8 csg set 609' cwc

4 1/2 csg set 3699' cw 125 sk cem. PFS (3307'-3310')

Set 4 1/2 wood plug at 3200' -poured 10' sand- dumped 4 sk cem W/dump bailer. (3200'-3165')

Cutoff & recovered 2007' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water -released 8 5/8 plug & followed

with 70 sk 50-50 poz 6% displaced with 7 sk gel & water & capped with 30 sk

50-50 poz 6% & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 10-24-78

NO. 8363-W