

P

KANSAS
15051-06764-00-01
STATE CORPORATION COMMISSION

Form CP-3
Rev. 6-4-68

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.
Complete Address Route # 2 Victoria, Kansas 67671
Lease Name Ubert "B" Well No. 2
Location SW SW SE Sec. 1 Twp. 13 Rge. (E) (W) 18
County Ellis Total Depth 3871'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling, Inc.
Address Box 1082 Great Bend, Kansas License No. 623
Operation Completed: Hour 11:30 A Day 8 Month 12 Year 1973

The above well was plugged as follows:

Total Depth 3871' 8 5/8 csg set at 193' ewe 150 sk.

4 1/2 csg set at 3680' ewe 650 sk. No pipe recovered.

Filled 4 1/2 csg W/d to 3665' dumped 4 sk cem W/dump bailer.

~~Filled 4 1/2 csg with cement to 3665' dumped 4 sk cem W/dump bailer.~~

Filled 4 1/2 csg with mud to 500' -set wood plug and dumped 4 sk cem.

Filled 4 1/2 csg with 2 1/2 yds readymix cem from 500' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mansury
Well Plugging Supervisor

DATE 12/10/73
INV. NO. 8262-U