

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-051-06763-00-18

LOCATION CE 1/2 SE SW

SEC. 1 TWP. 13 RGE. 18 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Crissman

Operator Doley Oil Co Address 473 Hays, Kans

Field Umbert County Ellis

Total Depth 3669 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 160'ncirculated with cement. 5 1/2" 3669' with
100 sax cement behind.

Perforated at 3623'. Filled with mud to 3620', set 4 sax
cement with dump bailer, pulled 770' 5 1/2", filled hole with
heavy mud to 160', set rock bridge and 15 sax cement.
filled with heavy mud to 40', set rock bridge and 10 sax
cement to bottom cellar.

REC
STATE OF KANSAS

11-25-50
NOV 25 1950

J. Edgar Doley
District Conservation Agent

Date 11-21-50

PLUGGING
FILE SEC 1 T 13 R 18 W
BOOK PAGE 44 LINE 37