

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,770-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Energy Reserves Group, Inc.

Complete Address 917 N. Water, Wichita, Ks. 67201

Lease Name p. Pfeifer

Well No. A-1

Location C of SW SW NE

Sec. 15 Twp. 13 Rge. 18 (East) (West)

County Ellis

Total Depth 3790'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&AXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling, Inc.

Address P.O. Box 448, Eldorado, Ks. 67042

License No. \_\_\_\_\_

Operation Completed: Hour: 9:45 PM Day: 7 Month: FEB. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-115' S.P. cuc. W/ 215 sacks 50/50 posmix-4% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 780' with 70 sacks cement

2nd plug @ 210' with 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 115' of 8 5/8"

*PCUD  
02-16-82*

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

02-17-82  
8445-U