



15-051-20688-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 - 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hicks of Dreiling Drlg. has this date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt

Complete Address: Box 370 Hays, Ks.

Lease Name: Bruill (Beull) Well No. 1

Location: SW SW NE Sec. 25 Twp. 13 Rge. (E)(W) 19

County: Ellis Total Depth 3670' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Hicks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 420' and displace
50 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent