



15-051-20169-10-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
DEC 13 1967
12-13-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Miller of L. J. Dreiling & Sons, Inc. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt

Complete Address: Drawer 370 Hays, Ks.

Lease Name: Befort "A" Well No. 1

Location: SE SE NW Sec. 23 Twp. 13 Rge. 19 (E)(W) X

County: Ellis Total Depth 3706 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 660' and displace
100 cs cement thru drill pipe. Heavy mud to 150' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Leo J. [Signature]
Conservation Division Agent