

15-009-20206-00-00

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charles Harre of Thoroughbred Drilling Company has this date requested permission to plug the following described well:

Mr. J. A. Hayes, Jr. guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: 4th. Floor, Petroleum Bldg., Tulsa, Oklahoma

Lease Name: Harriet Bird Well No. # 1

Location: NW SE NW Sec. 33 Twp. 18 Rge. 15 (E)(W) W

County: Barton Total Depth 3498 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Charles Harre was instructed to plug the well as follows:

8 5/8" 879' Cwc.

Circulated hole with heavy mud to 850', set plug, & displaced 30 sax cement thru drill pipe. Mud to 350', set plug, & displaced 25 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Globe Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don L. Brown
Conservation Division Agent