



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-051-22679-00-00  
15-051-22679-00-00

Dear Sir:

Mr. Gerald Brostek of Aspen Oil Inc. has this  
date requested permission to plug the following described well:

Operator's Full Name: Aspen Oil Inc.

Complete Address: 7701 E. Kellogg Suite 575, Wichita, Ks. 67207

Lease Name: Ubert N.W. Werth Well No. #1

Location: NE SW NE Sec. 2 Twp. 13 Rge. 18 (E) (W)

County: Ellis Total Depth: 3650'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A XXX

Other well as hereafter indicated:       

Mr. Brostek was instructed to plug the well as follows:

8 5/8" 554' S.P. cuc. w/300 sacks common 2% Gel-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel-3% Cal.Cl. and 8 5/8" plug.

Spot w/ drill stem with heavy mud between all plugs.

1st plug @ 750' W/70 sacks cement

2nd plug @ 310' W/40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' w/ 10 sacks cement

Circulate 10 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1982

Very truly yours,

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
Conservation Division Agent