

15-051-20023-00-00

15-051-20023-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67209

WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 9 1967
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Buchheister of John O. Farmer Drlg. Inc. has this
 date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer Inc.

Complete Address: 370 W. Wichita Ave. Russell, Kansas

Lease Name: Bolifka Well No. 2

Location: SE SW NE Sec. 8 Twp. 13 Rge. 18 (E)(W) X

County Ellis Total Depth 3812' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buchheister was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace
25 sc cement thru drill pipe, Heavy mud to 160' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Rio Maxwell
 Conservation Division Agent