

State of Kansas



FORM CP-2

15-051-22335-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Wiesner of Helberg Oil Company has this date requested permission to plug the following described well:

Operator's Full Name: Tom Wiesner Oil Company

Complete Address: 3007 Indian Trail, Hays, Kansas 67601

Lease Name: Frank A. Schmidt Well No. #3

Location: SW/NE/SW-330' from North line Sec. 16 Twp. 13 Rge. 17 (E) W1
120' from East Line.

County: Ellis Total Depth: 3660

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated:

Mr. Tom Wiesner was instructed to plug the well as follows:

8 5/8"-203' sp. cuc. w/145 common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug@ 720 ft. with 70 sacks cement

2nd plug@ 180 ft. with 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement.

5 sacks cement in rat hole.

Very truly yours,


Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP - 9 1981
CONSERVATION DIVISION
WICHITA, KANSAS