

KANSAS

FORM CP-3
Rev. 5-5-81STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORTAPI Number 15- (none) -051-19392-00-02
051-19392-00-02200 Colorado Derby Bldg.
Wichita, KS 67202Operator's Full Name Gulf Oil Exploration & Production CompanyComplete Address P. O. Box 12116, Oklahoma City, Oklahoma 73157Lease Name Crissman "B" Well No. #1-WILocation SE/NE/NE Sec. 2 Twp. 13S Rge. 18 (East) (West)County Ellis Total Depth 3636'Abandoned Oil Well Gas Well Input Well XX SWD Well D & A Other well as hereafter indicated Plugging Contractor Gulf Oil Exploration & Production CompanyAddress P. O. Box 12116, Oklahoma City, Oklahoma 73157 License No. Operation Completed: Hour: 4:45PM Day: 6th Month: Oct. Year: 19 81Plugging Operations attended by Agent? All XX Part None

The above well was plugged as follows:

8 5/8" S.P. @ 1388' cuc. w/650 sacks common. 5 1/2" casing set at 3609' w/100 sacks common. T.D. 3636'. Plugged back to 3408'. Top perforation @ 3260'. Set bridge plug @ 3240'. Run 2 7/8" tubing in hole to 3238' and spotted w/10 sacks common cement. Shot 5 1/2" casing off at 2992' and pulled casing to 1430'. Spotted hole full of 36 funnel viscosity mud, followed w/50 sacks common-3% Gel-2% Cal. Cl.. Pulled casing to 260'. Pumped into 5 1/2" casing which was plugged. Pulled out all casing, pumped 9 sacks of Gel. and 40 sacks common-2% Gel.-3% Cal. Cl. cement to top of 8 5/8" SP 3 1/2 feet below ground level. Maximum Pressure was 600 pounds.

INV 01
DATE 11-13-82
6282-W

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

November 13, 1981

INVOICE NUMBER: 8282-W

TO: Gulf Oil Corporation ATTENTION: Dorretta Moore

P. O. Box 12116

Oklahoma City, OK 73157

PLUGGING ASSESSMENT AS FOLLOWS:

Crissman "B" #1-W1
SE NE NE Sec. 2-13S-18W
Willis
3636'

\$118.17

15-051-19392-00-02
15-051-19392-00-02

NOTE: We also need the following before our file is completed:


- ☒ Well Plugging Record (CP-4)
- ☐ Well Log
- ☐ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



Administrator

Mr. Gilbert Scheck 2202 Canterbury Road Hays, Ks. 67601

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE