

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-051-00699-00-00

FILE NO. 15-051-00699-00-00

LOCATION NW SE NW

SEC. 2 TWP. 13 RGE. 18 <sup>W</sup>

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Shutts

Operator Doley Oil Co Address Dox 473 Hays, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3688 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 172' Circulated with cement-5 1/2" at 3657' with 100 sax.  
Filled with mud to 3605, run 6 sax cement with bailer, pulled  
2800' of 5 1/2", filled hole with heavy mud to 172' set rock  
bridge and 15 sax cement - filled with heavy mud to 35', set  
rock bridge and 10 sax cement filling hole to bottom cellar.

Eddon [Signature]  
District Conservation Agent

Date 1-21-50

**PLUGGING**  
FILE SEC 2 T 13 R 18W  
BOOK PAGE 135 LINE 9

X