

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company 15-051-20691-00-00

Complete Address 217 N. Water Wichita, Kansas

Lease Name Jack R. Nicholson Well No. 1 - V

Location SE NW NW Sec. 16 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3724

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:45 P Day 16 Month 12 Year 1970

The above well was plugged as follows:

RTD 3724: 8 5/8 csg set at 249' cwc Gmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 100 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12/21/70

INV. NO. 3099-W