

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-21, 969-0000

245 North Water
Wichita, KS 67202

Operator's Full Name LIBERTY ENTERPRISES, INC.

Complete Address 308 WEST MILL, PLAINVILLE, KANS. 67663

Lease Name NICHOLSON Well No. #1

Location C. E 1/2 - SW - NW Sec. 16 Twp. 12 Rge. 18 (East) (West)

County ELLIS Total Depth 3725 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor BIG-HAT DRILLING (GARY PUGH)

Address Box 18145 - WICHITA, KS License No. _____

Operation Completed: Hour 10:15 PM Day 22 Month NOV. Year 1980

The above well was plugged as follows:

8 5/8" 267 FT SD. CUC w/ 165 ST COMMON - 2% GEL. - 3% CA-CL.

ORDERED 110 ST 50/50 POZMIX 6% GEL. & 8 5/8" PLUG. - ENV. 2127 G.L.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1 ST PLUG. @ 660 FT w/ 70 ST CMT.

2 ND PLUG. @ 240 FT w/ 25 ST CMT.

3 RD PLUG. - SOLID BRIDGE - HULLS - PLUG @ 40 FT TO 0 w/ 10 ST CMT.

5 ST IN RHT HOLE.

CEMENTED BY ALLIED NOV 26 1980

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

12-11-80
INV. NO. 3724-W