

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
S. STATE CORPORATION COMMISSION

MAR 9 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-051-20023-00-00
15-051-20023-00-00

Operator's Full Name John O. Farmer, Inc.

Complete Address: 370 W. Wichita Ave. Russell, Kansas

Lease Name Polifka Well No. 2

Location SE SW NE Sec. 8 Twp. 13 Rge. 18 (E) (W) X

County Ellis Total Depth 3812'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 6:15 P Day 7 Month 3 Year 1967

The Above well was plugged as follows:

RTD 3812' 8 5/8 csg set at 166' cwc 135 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 160' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo J. Mandy
Well Plugging Supervisor

DATE 3/9/67

INV. NO. 4887-W