

KANSAS

R
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-051-20527-00-00

15-051-20527-00-00

Operator's Full Name Okmar Oil Company

Complete Address 1130 Wichita Plaza Wichita, Kansas 67202

Lease Name Polifka Well No. 1

Location SE SE NW Sec. 8 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3767'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:30P Day 19 Month 11 Year 1969

The above well was plugged as follows:

RTD 3767' 8 5/8 csg set at 171' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 100 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murray
Well Plugging Supervisor

INVOICED

DATE 11/21/69
INV. NO. 886-4