

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-051-30320-00-00
15-051-30320-00-00

Operator's Full Name John O. Farmer, Inc.

Complete Address 370 W. Wichita Russell, Kansas 67665

Lease Name Polifka Well No. 1

Location NW NW SE Sec. 8 Twp. 13 Rge. (E) (W) 18

County Ellis Total Depth 3812'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 5P Day 10 Month 1 2 Year 1970

The above well was plugged as follows:

Total Depth 3812' 8 5/8 csg set at 168' cwc.

4 1/2 csg set at 3796' cw 100 sk cmt.

4 1/2 csg perf. (3475-3522)

Set 4 1/2 wood plug at 3450'. Poured 10 gal sd and dumped 4 sk cmt W/dump bailer.

Cutoff and recovered 3000' of 4 1/2 Csg.

Pumped thru 8 5/8 plug container with 30 sk gel W/5 sk hulls, plug and 150 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Murray
Well Plugging Supervisor

DATE 2/16/70
INV. NO. 1432-W