

1

KANSAS
STATE CORPORATION COMMISSION
15-051-05539-00-00
WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 98-42 Location: SE NW NE
County: Ellis Sec. 16 Twp. 13 Rge. 17 (E) (W)
Name of Field or Pool: _____ Total Depth: 3589

I have this date completed supervision of plugging of:

Well No. Unit R | Lease Catherine Unit "B"
Operator's Full Name Mallonee Drg Co Inc.
Complete Address: 820 Union Center Wichita, Kans
Plugging Contractor: West Supply Co

Address: _____ License No. 14

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 3PM Day 10 Month 5 Year 58

The above well was plugged as follows:

8 5/8" at 137' circulated with cement - 5 1/2" 3588' with 7/8 sax cement behind.

Dumped 4 sax cement on bottom with dump bailer - pulled 3012' 5 1/2" to 500', circulated hole with heavy mud (Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 200', displaced 20 sax cement through 5 1/2" - heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co pump truck.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Edson Teal*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: *J. Lewis Brock*
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks: _____

PLUGGING
FILE SEC 16 T 13 R 17W
BOOK PAGE 98 LIT 42