

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20697-00-00  
Spot: SESENW Sec/Twnshp/Rge: 3-9S-27W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: MOSIER A Well #: 4  
County: SHERIDAN Total Vertical Depth: 4043 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	247	0	175 SX
T1	2.875	4010		
PROD	5.5	4042	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/07/2011 1:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 350 sxs 60/40 ozmix - 4% gel - 600# hulls - 12 sxs gel.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/07/2011 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 247' w/175 sxs cement.  
5 1/2" production casing set at 4042' w/175 sxs cement.  
TD 4043'. PBTD 4017'.  
Perforated production casing at 2275' - 1380' - 300'.  
Ran tubing to 3934' - pumped 12 sxs gel - followed with 50 sxs cement mixed with 200# hulls.  
Pulled tubing to 2283' - pumped 120 sxs cement mixed with 200# hulls.  
Pulled tubing to 1201' - circulated cement to surface with 125 sxs cement mixed with 200# hulls.  
Pulled tubing to surface.  
Connected to 5 1/2" production casing - pumped 55 sxs cement.  
Cement to surface from 8 5/8" surface casing.  
Plug complete.

Perfs:

Top	Bot	Thru	Comments
3967	3969		LKC K
3947	3949		LKC J
3899	3901		LKC H
3850	3852		LKC F
3844	3846		LKC E
3761	3764		TOR

RECEIVED  
JAN 24 2011  
1-24-11  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34066.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

JAN 11 2011