

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22645-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 13-7S-20W  
990 feet from S Section Line, 990 feet from W Section Line  
Lease Name: SCHNEIDER Well #: 3  
County: ROOKS Total Vertical Depth: 3570 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261	0	165 SX CMT
PROD	4.5	3569	0	250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2011 12:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls - 8 sxs gel.  
DV Tool at 1580' w/450 sxs. PBTD 3563'.  
Fluids 500' - casing leaks 2189' - 2196'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2011 4:00 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Murfin RIH with tubing to 3110'.  
Allied rigged to tubing and mixed and pumped 8 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.  
Pulled tubing to 1650'. Allied rigged to tubing and mixed and pumped 100 sxs cement with 250# hulls mixed in to circulate cement to pit area.  
Pulled tubing. Topped off 4 1/2" casing with 15 sxs cement - hole standing full.  
Rigged to 8 5/8" casing with a swedge - pumped 5 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

**Perfs:**

Top	Bot	Thru	Comments
3503	3513		ARBUCKLE
3254	3258		LKC A
3244	3296		LKC B
3236	3239		TORONTO

Remarks: ALLIED CEMENTING COMPANY-TICKET #34085.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

KANSAS CORPORATION COMMISSION Form CP-2/3

1-18-11  
JAN 18 2011

RECEIVED

JAN 14 2011