

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22681-00-00  
Spot: SESESW Sec/Twnshp/Rge: 13-7S-20W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SCHNEIDER Well #: 4  
County: ROOKS Total Vertical Depth: 3530 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	238	0	160 SX
PROD	5.5	3530	0	115 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/17/2011 10:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.  
DV Tool 1561' w/400 sxs.  
Wireline TD 3500'. Fluids 1200'.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 01/17/2011 12:45 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Murfin RIH with tubing to 3408'.  
Allied rigged to tubing - mixed and pumped 15 sxs gel - followed with 50 sxs  
60/40 pozmix - 4% gel with 150# hulls mixed in.  
Pulled tubing to 1617'. Allied rigged to tubing and pumped 120 sxs cement with 250# hulls  
mixed in to circulate cement to surface.  
Pulled tubing. Topped off 5 1/2" casing with 15 sxs cement.  
Hole standing full.  
Rigged to 8 5/8" - pumped 2 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.

**Perfs:**


Top	Bot	Thru	Comments
3482	3492		ARBUCKLE

Remarks: ALLIED CEMENTING COMPANY-TICKET #034072.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

JAN 20 2011

KCC WICHITA

JAN 18 2011