

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20400-00-00  
Spot: S2NWNESE Sec/Twnshp/Rge: 30-11S-19W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: ZERFAS Well #: 1  
County: ELLIS Total Vertical Depth: 3697 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	198	0	175 SX
PROD	5.5	3682	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2010 11:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (784) 483-1314

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel spacer.  
04/07/1972 - Squeezed at 1182' w/110 sxs.  
11/12/1974 - Squeezed at 890' - 1165' w/225 sxs and 125 sxs.  
05/27/1981 - Squeezed at 2772' - 2787' w/125 sxs.  
05/30/1981 - Squeezed at 1620' - 1637' w/75 sxs and 1821' - 1852' w/300 sxs.  
06/30/1981 - Squeezed at 1818' - 1852' w/125 sxs.  
01/04/2002 - Squeezed at 2060' - 2092' w/250 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/16/2010 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Ran tubing to 3591' - pumped 11 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 2100' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1020' - pumped 110 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled all tubing. Topped off 5 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 5 1/2" annulus - pumped 25 sxs 60/40 pozmix - 4% gel.  
S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: TBG

RECEIVED  
DEC 21 2010  
KCC WICHITA

District: 04 Signed Pat Bedore  
(TECHNICIAN) CM