

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20813-00-02
Spot: SESW Sec/Twnshp/Rge: 11-32S-34W
654 feet from S Section Line, 3196 feet from E Section Line
Lease Name: BOLES Well #: 4-11
County: SEWARD Total Vertical Depth: 5839 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5416		WITH 5 SX CMT
SURF	8.625	1679		WITH 750 SX CMT
DVT		3003		WITH 360 SX CMT
PROD	5.5	5839	0	WITH 510 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/16/2010 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5416' WITH 2 SX CMT. PLUG AT 1700' WITH 80 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2010 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

****ATTEMPTED TO CUT CASING AT 1780', 1735', 1170', & 776' COULD NOT PULL.****
CIBP @ 5416' WITH 5 SX CMT. PLUG AT 3030' WITH 25 SX CMT. RIH W/TBG & PACKER TO 1200'. PRESSURED TO 1000#, COULDN'T PUMP IN TO. POOH TO 600' & PRESSURED TO 500#, COULDN'T PUMP IN TO. POOH WITH TBG & PACKER. RIH W/TBG TO 1820' & PUMP 30 SX CMT. POOH TO 1200' & PUMPED 120 SX CMT. FILLED 5 1/2" TO SURFACE. TIED ONTO 8 5/8" & 5 1/2" ANNULUS & PUMPED 7 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
5466	5486		MORROW

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

SEP 21 2010

KCC DODGE CITY

Signed

Jack MacLuskey
RECEIVED (TECHNICIAN)

SEP 30 2010

KCC WICHITA

Form CP 273