

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20369-00-01
Spot: NWNESE Sec/Twnshp/Rge: 15-33S-38W
2310 feet from S Section Line, 1250 feet from E Section Line
Lease Name: DAVIS C Well #: 2
County: STEVENS Total Vertical Depth: 6228 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5663		WITH 2 SX CMT
CIBP		5800		
SURF	8.625	1702		WITH 800 SX CMT
DVT		3155		
PROD	4.5	6217	0	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/22/2010 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2010 10:00 AM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

CIBP @ 5663' WITH 2 SX CMT. PLUG AT 3205' WITH 100# HULLS & 40 SX CMT. PLUG AT 1750' WITH 120 SX CMT. PERFORATE 4 1/2" @ 900'. TIE ONTO 4 1/2" & PUMPED 300 SX CMT. GOOD BLOW ON 4 1/2" & 8 5/8" ANNULUS UNTIL CIRCULATION, WENT ON VACUUM. 7/26/10: TAGGED TOC @ 780'. PERFORATE 4 1/2" @ 625'. PUMPED 200 SX CMT INTO 4 1/2". CIRCULATED CMT TO SURFACE & FILLED 4 1/2" X 8 5/8" ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5713	5719		

Remarks: USED 60/40 POZMIZ 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
AUG - 6 2010
KCC DODGE CITY

Signed

Jack Macclash
(TECHNICIAN)

RECEIVED
AUG 16 2010

Form CP-2/3

WICHITA