

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10221-00-01  
Spot: SENE Sec/Twnshp/Rge: 29-28S-34W  
1980 feet from N Section Line, 660 feet from E Section Line  
Lease Name: J D G STUCKY Well #: 1-29  
County: HASKELL Total Vertical Depth: 5503 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 500  
DALLAS, TX 75240

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 5222       |             | WITH 2 SX CMT   |
| CIBP   |       | 5395       |             |                 |
| SURF   | 8.625 | 1866       |             | WITH 850 SX CMT |
| DVT    |       | 2984       |             |                 |
| PROD   | 5.5   | 5502       | 1947        | WITH 100 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2010 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5240' WITH 2 SX CMT. PLUG AT 1900' WITH 80 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2010 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5222' WITH 2 SX CMT. 1ST PLUG AT 1900' WITH 80 SX CMT. 2ND PLUG AT 680' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 5430 | 5438 |      |          |

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

AUG - 6 2010

KCC DODGE CITY

Signed

*Jack MacLaskey*  
(TECHNICIAN)

RECEIVED

AUG 16 2010

KCC WICHITA

Form CP-2/3