

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21531-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 20-31S-38W
3095 feet from S Section Line, 4736 feet from E Section Line
Lease Name: SPIKES A Well #: 4-A
County: STEVENS Total Vertical Depth: 6000 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5600		WITH 5 SX CMT
CIBP		5670		
CIBP		5708		
SURF	8.625	1717		
PROD	5.5	5893	1789	

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/21/2010 2:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5590' WITH 2 SX CMT. PLUG AT 1750' WITH 80 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL
Date/Time Plugging Completed: 10/22/2010 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5600' WITH 5 SX CMT. 1ST PLUG AT 1750' WITH 80 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. NO CIRCULATION. TOP OF FLUID @ 380'. SDON. 10/22/10: TAGGED TOC @ 653'. PUMPED 50 SX CMT AT 640'. GOOD CIRCULATION. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5715	5719		
5674	5688		
5642	5666		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
NOV 08 2010
KCC WICHITA

District: 01

RECEIVED

OCT 28 2010

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

[Signature]
KCC