

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20918-00-01
Spot: SWNE Sec/Twnshp/Rge: 23-26S-18W
1996 feet from N Section Line, 2084 feet from E Section Line
Lease Name: CROCKETT Well #: LOWWO
County: EDWARDS Total Vertical Depth: 4716 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4085		WITH 2 SX CMT
CIBP		4620		
SURF	8.625	367		WITH 275 SX CMT
PC		3510		
PROD	5.5	4710	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/02/2010 4:00 PM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: JEFF BURKE Company: MID-CONTINENT ENERGY Phone: (316) 265-9501

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 11/02/2010 6:45 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SET CIBP @ 4085' WITH 2 SX CMT, THEN SHOT PERFS AT 390'. RAN TBG TO 1200' & SPOT 25 SX CMT. PULL TBG TO 390' & PUMPED 125 SX CMT CIRCULATING 14 SX CMT TO THE PIT. PULL TBG & TOPPED OFF WITH 3 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4686	4690		
4552	4562		
4542	4546		
4532	4536		
4247	4253		
4214	4218		

Remarks: USED 60/40 POXMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

RECEIVED
NOV 10 2010
KCC DODGE CITY

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
NOV 15 2010
KCC WICHITA