

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24272-00-00
Spot: NWSENE Sec/Twnshp/Rge: 7-33S-8E
4297 feet from S Section Line, 848 feet from E Section Line
Lease Name: FULSOM Well #: 1
County: COWLEY Total Vertical Depth: 2690 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	451		220 SX
T1	2.375	2598		
PROD	4.5	2690	1200	130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2010 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-0020

Proposed Plugging Method: AS PER KCC RULES & REGS, PER DLB, SANT TO 2550, W/4SXS, 500 TO SURFACE 60/40 4%.

Plugging Proposal Received By: DAVID BOLLENBACK WitnessType: PARTIAL
Date/Time Plugging Completed: 08/10/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2550', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 1200', LAYED DOWN 4-1/2" CASING @ 500'. SWEDGED INTO 4-1/2" CASING, CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & PUMPED 173 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. FINISHED LAYING DOWN 4-1/2" CASING AND TOPPED WELL OFF TO SURFACE W/CEMENT. PLUG DOWN 8-11-2010, 1:00 PM. CONSOLIDATED CEMENT TICKET # 28417.

Perfs:

Top	Bot	Thru	Comments
2600	2603	CSG	
2598	2601	CSG	

Remarks:
Plugged through: CSG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
OCT 2 2010

Form CP-2/3

KCC WICHITA

SK