

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21625-00-00
Spot: NWSENE Sec/Twnshp/Rge: 33-18S-20W
3646 feet from S Section Line, 931 feet from E Section Line
Lease Name: JANKE Well #: 1
County: RUSH Total Vertical Depth: 4161 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		700		
CIBP		3765		WITH 2 SX CMT
SURF	8.625	235		WITH 175 SX CMT
PROD	5.5	4147	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2010 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RODNEY BRIN Company: MID-CONTINENT ENERGY Phone: (316) 265-9501

Proposed Plugging Method: SET CIBP @ 4100' & 2 SX CMT. SET CIBP @ 700'. PERFORATE 5 1/2" @ 650'. RUN TBG & CIRCULATE CMT UP BOTH STRINGS OF CASING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2010 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COULDN'T GET PAST 3788'. SET CIBP @ 3765' WITH 2 SX CMT ON TOP WITH DUMP BAILER. SET CIBP @ 700'. PERFORATED 5 1/2" @ 650'. RAN TBG TO 665'. PUMPED 85 SX CMT CIRCULATING UP 5 1/2". NO CIRCULATION ON 8 5/8". PULLED TBG OUT. PUMPED 80 SX CMT DOWN 5 1/2". MAXIMUM PRESSURE 450 PSIG. SHUT IN PRESSURE 350 PSIG. PUMPED 100 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 400 PSIG. SHUT IN PRESSURE 200 PSIG.

Perfs:

Top	Bot	Thru	Comments
4147	4161	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
SEP - 3 2010
KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
SEP 10 2010
KCC WICHITA